



MANAFORT BROTHERS INCORPORATED

ROUTE 8 BRIDGES REMOVAL & REPLACEMENT

Highway & Bridges



PROJECT

Route 8 Bridges Removal & Replacement

MARKETS

Highway & Bridges
Demolition, Rehabilitation and Abatement
Concrete
Alternative Project Delivery

CONTRACT TYPE

Design Build Prime Contractor

PROJECT OWNER

The Connecticut Department of Transportation

LOCATION

Bridgeport, CT

AWARDS

- CMAA 2016 Connecticut Infrastructure Project of the Year
- CMAA 2017 New England Infrastructure Project of the Year
- CMAA 2017 National Project Achievement Award
- ACEC 2017 Connecticut Engineering Excellence Award
- ACEC 2017 National Recognition Engineering Excellence Award
- CTDOT 2016 Arthur Gruhn Excellence in Construction Award
- DBIA 2016 New England Highway Infrastructure Gold Award
- DBIA 2017 National Award of Merit
- ASCE 2017 Connecticut Construction ACE Award
- ASCE 2017 Connecticut Structural ACE Award

The CTDOT – Design / Build Removal and Replacement of Bridges 03761, 03762, 03764, and 03765 along RT 8 in Bridgeport, CT was the first Design / Build Project performed for The Connecticut Department of Transportation. This Accelerated Bridge Construction Project consisted of the demolition of 16 bridge spans and the design and construction of 10 new replacement bridge spans. The work included demolition of the existing bridges, new bridge superstructures, bridge substructure repairs and modifications, cast in place concrete walls, earthwork, and roadway construction.

All work was performed using Accelerated Construction Techniques. Manafort collaborated with it's Design / Build Partner WSP Parsons Brinckerhoff to develop a detailed design that supported these Accelerated Construction Techniques most notably including onsite prefabrication of the bridge superstructure units. The bridge superstructure demolition, reconstruction, over 30,000 cy of roadway and structural fill, and highway approach work was all completed ahead of schedule, four days less than the two, 14 day shutdown periods allowed by CTDOT. Through detailed planning, prefabrication, scheduling, and coordination, it is estimated that Manafort completed two construction seasons worth of work during these two 14 day shutdown periods.

The project was completed under budget, ahead of schedule, and was the recipient of a number of regional and national industry awards. Manafort served as The Design / Build Prime Contractor for the project and self-performed a majority of the work including demolition, excavation, cast in place concrete, onsite prefabrication of bridge superstructure units, road and highway work.



CORPORATE OFFICE

414 New Britain Avenue,
PO Box 99
Plainville, CT 06062
Phone: 860.229.4853

REGIONAL OFFICE

265 Southwest Cutoff
Worcester, MA 01604
Phone: 774.512.3800

REGIONAL OFFICE

24 Martin Street
Cumberland, RI
Phone: 401.333.2550

REGIONAL OFFICE

318 Bear Hill Road, Suite 10
Waltham, MA 02451
Phone: 781.328.2365

REGIONAL OFFICE

204 Mill Street
Bristol, PA 19007
Phone: 267.812.5454